



## Benbecula Airport, Phase 2 Repairs - Case Study



Contract: Benbecula Airport, Phase 2 Repairs

Client: Highland & Islands Airports Ltd

Consultant: Pick Everard

Contract Duration: 22 weeks (Jan 2015—June 2015)

Contract Value: >£500,000



These works were designed to strengthen a portion of the existing Phase 2 works, carry out repairs to areas of the defences and prevent the continued erosion of beach material from the western boundary of Benbecula Airport on the Western Isles.

The works involved the Installation of 90 linear metres of coastal protection consisting of rock armour and concrete. The 5-7tonne rock Armour was supplied from Askernish Quarry. Repair of damaged reno mattress, comprising stone refill and lacing on new lids. Landscaping and replanting of dune areas disturbed during construction of the works. Restoration of the coast alignment using excavated material.

Highlands and Islands Airport Limited  
Benbecula Airport  
Balivanich  
Isle of Benbecula  
HS7 5LW



### Summary



Training was carried out on site by reno mattress supplier MacAffari, to ensure our workforce were adequately trained in the installation and tying of mattresses. This provided the client with a quality finished product.